



1 TELEPHONE / DATA / COMMUNICATIONS RISER DIAGRAM
E5.3

- NOTES**
- FLOOR PENETRATION FROM BELOW. WHERE CONDUITS ENTER SPACE AND TERMINATE IN SAME SPACE EC SHALL EXTEND CONDUITS 1'-0" AFF.
 - FLOOR PENETRATION FROM ABOVE. WHERE CONDUITS ENTER SPACE AND TERMINATE IN SAME SPACE EC SHALL EXTEND CONDUITS 1'-0" BELOW AFF.
 - EXTERIOR BUILDING WALL PENETRATION EC SHALL EXTEND CONDUIT 5'-0" OUTSIDE OF BUILDING WALL.
 - EC SHALL PROVIDE AND INSTALL PULL STRING IN EACH CONDUIT.
 - AT EACH COMMUNICATION DATA OUTLET EC SHALL PROVIDE AND INSTALL 2" x 4" OUTLET BOX WITH (1) 3/4" EMT FROM OUTLET BOX TO 12" ABOVE LAY-IN CEILING WITH (1) DATA CABLE AND (1) TELEPHONE CABLE TO DESIGNATED FLOOR TELEX/DATA ROOM. EC SHALL COIL 14'-0" OF CABLE AT DATA/TELECOM ROOM FOR TERMINATIONS BY DATA CONTRACTOR. EC SHALL COORDINATE EXACT CABLE TYPE AND ALL REQUIREMENTS WITH DATA CONTRACTOR. EC SHALL USE CAT-6 PLENUM RATED UNLESS DIRECTED OTHERWISE DATA CONTRACTOR.

THE EAST GROUP, P.A.
CORPORATE SEAL
N.C.

DATE	REV	BY	CHK	APP	DWM	DUM	ISSUED FOR CONSTRUCTION
05-30-04	A						

EXISTING GUC BUILDING
ELECTRICAL TELE/DATA
COMMUNICATIONS RISER

CITY OF GREENVILLE
ADMINISTRATIVE OFFICES
ADDITIONS & RFP RENOVATIONS
GREENVILLE, NORTH CAROLINA

THE EAST GROUP, P.A.
Architectural • Mechanical • Electrical • Plumbing • Fire Protection
200 S. W. Lee St., Greenville, NC 27834 • 252-433-2800

DRAWING TITLE	PROJECT TITLE	DATE	REV	BY	CHK	APP	DWM	DUM
ELECTRICAL	EXISTING GUC BUILDING ELECTRICAL TELE/DATA COMMUNICATIONS RISER	05/07/04						

E5.3

PROJECT NO. 200.30141