

**CITY OF GREENVILLE
RECREATION AND PARKS
H. BOYD LEE PARK HVAC MODIFICATIONS**

ADDENDUM NO. 3

The following corrections, clarifications, or supplemental information is to be incorporated into the Contractor's Bid to perform the Work.

CLARIFICATIONS

New exposed conduits shall be painted to match existing.

Exterior wall conduit penetrations denoted by notes 3 and 4 on Drawing E2.1 shall be made above 84" AFF in the storage room.

END OF ADDENDUM NO. 3