

## **GTAC Fiber Optic Install**

The City of Greenville NC is soliciting bids for the following items:

- 1) The installation of approximately 250 feet of 2 inch flexible conduit with pull string and locate wire along the path depicted by the installation diagram. This installation method for this conduit is via boring, not direct burial.
- 2) Installation and termination 48 strands of single mode fiber optic cabling. The installation endpoints are from the 2<sup>nd</sup> floor of City Hall Room 238 located at 200 W 5th St. to the 1<sup>st</sup> floor communications room of the new Greenville Transportation Activity Center (GTAC) located on the corner of Pitt St and Bonners Lane. The installation path is depicted by the installation diagram

This is a turn-key job with all labor, materials, and utility locate requests provided by the cable contractor. The Contractor is required to verify footages and items needed for installation as a part of the bid response.

Attached is a diagram (GTAC\_FO.PDF) of the cable routing and specifications. Note all comment blocks as a part of this project.

Must be able to begin installation as early as March 31, 2018.

Federal FTA Clause:

Since this project is being paid for with Federal Transit Authority (FTA) funds, the installer must comply with the clauses stated within the attached document "GTAC Project FTA Clauses IT.DOC".