

To: All Interested Bidders
From: Victor Long
RE: Laughinghouse Drive Stream Enhancement Project, Addendum #1
Date: June 4, 2018

The following items clarify, add to, delete from and/or otherwise change and supersede information previously issued to you in the Bid Documents for the above-referenced project. As such, said items shall be considered part of the contract and receipt of this addendum shall be acknowledged appropriately in the bid package. Please review the following items carefully and adjust your proposal accordingly.

Pre-bid Minutes and Clarifications

1. The slope of the stream shall be graded at a 2:1 slope or greater where possible.
2. The Contractor shall begin onsite work on or before 30 calendar days from the notice to proceed of the contract and shall notify the City in writing a minimum of 7 calendar days in advance of the date on which the Contractor intends to begin work. The Contractor shall diligently pursue the work to completion within 14 calendar days from beginning work. Voluntary shutdown or slowing of operations by the Contractor shall not relieve the Contractor of the responsibility to complete the work within the time specified in the contract.
3. It was confirmed at the pre-bid that a performance bond and a payment bond will be required
4. Trees over 6 inches in diameter that are in the project will be removed by others before construction starts.
5. There will be 240 live plants in addition to the seeding and mulching for stabilization of the slope. Attached to the addendum is a list of plants suitable for live planting in the coastal plains region. The Contractor can choose any plant from the list that states that it is for the coastal plain. The city would like to see at least 5 different varieties for plant diversity.
6. All disturbed areas will be seeded and mulched with a contractors mix.
7. Access to the site will be through a temporary construction easement provided by the property owner on the Laughinghouse Drive side of the stream. This easement will show any trees and plants that will need to be protected. Any trees and plants that the residents would like to save will need to be removed by the property owners prior to construction. The easement will also provide a clear path for access to the project.
8. The Contractor will need to use the bid form attached to this addendum showing the new line item, Remove and replace chain link fence. The payment will be for the removal of the old chain link fencing and replacing with new chain link fence. The payment will be in linear feet and shall be for all the labor, materials and accessories required to complete the removal and installation.

9. For line item # 5 Channel Grading, the contract will have to move approximately 250 cubic yards of material, of that material about 120 cubic yards will be needed for fill and the rest hauled away.
10. The contractor that is awarded the contract will be provided a stream profile at the start of construction showing the new alignment of the stream.

Requests for additional information:

Any questions regarding this Addendum should be directed to Mr. Victor Long, at 252-329-4888 or email at vlong@greenvillenc.gov.