



ADDENDUM NO. 3

| | |
|--|-----------------------------------|
| Client / Facility: City of Greenville | TEG Project No.: 20200132 |
| Project Name: Convention Center Replacement of EPDM Roofs | Client Project No.: n/a |
| Addendum Date: February 12, 2021 | For Bids Due On: 2-16-2021 |

Corporate Office
 324 Evans St
 Greenville
 NC 27858
Tel 252.758.3746
Fax 252.830.3954

Raleigh Office
 4325 Lake Boone Trail
 Suite 311
 Raleigh
 NC 27607
Tel 919.784.9330
Fax 919.784.9331

www.eastgroup.com

This Addendum has become a part of the drawings and specifications for the above project.

Clarifications and additions

1. Subject to conformance with plans and specifications:
 - a. The gutters, downspouts, and drip edge may be shop fabricated - The copings shall remain pre-manufactured per Addendum 2.
 - b. Flex Membrane International Corp. is an accepted supplier of the 60 mil TPO membrane for Alternate 2.
2. Removal of the existing EPDM from all vertical surfaces and the tops of the parapet walls is required prior to installation of the new membrane. These surfaces include the parapet walls, all curbs, and the low slope roof to wall conditions shown in details 3/A7.2 and 4/A7.2.
3. Walkway Pads are not part of the scope of this project
4. Coating for all metal shall be a 2 coat Fluoropolymer finish

ENGINEERING
 -
ARCHITECTURE
 -
SURVEYING
 -
TECHNOLOGY
 -