

City of Greenville  
 Cedar Lane Drainage Improvements  
 Hazen Project Number: 31187-003

| Item No. | Description  | Unit | Estimated Quantity | Bid Unit Price | Bid Amount |
|----------|--|------|--------------------|----------------|------------|
| 1        | Mobilization and Demobilization (maximum 5% of Base Bid) | LS   | 1                  |                |            |
| 2        | Construction Surveying                                   | LS   | 1                  |                |            |
| 3        | Construction As-built                                    | LS   | 1                  |                |            |
| 4        | Traffic Control  | LS   | 1                  |                |            |
| 5        | Removal of Existing Concrete Pavement                    | SY   | 537                |                |            |
| 6        | Removal of Existing Asphalt Pavement                     | SY   | 3,900              |                |            |
| 7        | Removal of Existing Curb and Gutter                      | LF   | 1,270              |                |            |
| 8        | Milling Asphalt Pavement, 1.5" Depth                     | SY   | 1,200              |                |            |
| 9        | Drainage Pipe Removal (RCP)                              | LF   | 1,390              |                |            |
| 10       | Drainage Structure Removal                               | EA   | 18                 |                |            |
| 11       | Remove Existing Manhole                                  | EA   | 5                  |                |            |
| 12       | Remove and Dispose of Existing Gravity Sewer             | LF   | 150                |                |            |
| 13       | Removal and Disposal of 6-Inch AC Water Main             | LF   | 1,150              |                |            |
| 14       | Excavation   | CY   | 20                 |                |            |
| 15       | Select Fill (Road Fill)                                  | CY   | 30                 |                |            |
| 16       | #57 Stone, Pipe Bedding                                  | TN   | 330                |                |            |
| 17       | Topsoil  | CY   | 28                 |                |            |
| 18       | Select Tree Removal (8" - 18" dbh)                       | EA   | 9                  |                |            |
| 19       | Permanent Fertilizer, Seeding and Mulching               | SY   | 250                |                |            |
| 20       | Temporary Fertilizer, Seeding and Mulching               | SY   | 250                |                |            |
| 21       | Pedestrian/Tree Protection Fence                         | LF   | 320                |                |            |
| 22       | Concrete Washout Structure                               | EA   | 1                  |                |            |
| 23       | Inlet Protection   | EA   | 18                 |                |            |
| 24       | Silt Fence   | LF   | 730                |                |            |
| 25       | Rip Rap, Class B   | TN   | 30                 |                |            |
| 26       | 8" Aggregate Base Course                                 | TN   | 540                |                |            |
| 27       | 1.5" Asphalt Concrete Surface Course, Type S9.5B         | TN   | 430                |                |            |
| 28       | 2" Asphalt Concrete Intermediate Course, Type I19.0B     | TN   | 430                |                |            |
| 29       | Thermoplastic Pavement Marking Lines                     | LF   | 345                |                |            |
| 30       | Speed Cushions   | EA   | 3                  |                |            |

City of Greenville  
 Cedar Lane Drainage Improvements  
 Hazen Project Number: 31187-003

| Item No. | Description  | Unit | Estimated Quantity | Bid Unit Price | Bid Amount |
|----------|--|------|--------------------|----------------|------------|
| 31       | 2'-6" Concrete Curb and Gutter                           | LF   | 1,205              |                |            |
| 32       | Concrete Valley Gutter                                   | LF   | 180                |                |            |
| 33       | Concrete Curb Ramps                                      | EA   | 12                 |                |            |
| 34       | 4" Concrete Sidewalk (5' Width)                          | SY   | 620                |                |            |
| 35       | 6" Concrete Driveway                                     | SY   | 60                 |                |            |
| 36       | Evergreen Trees, 6' Height                               | EA   | 11                 |                |            |
| 37       | Masonry Drainage Structure (NCDOT Std. 840.02)           | EA   | 16                 |                |            |
| 38       | Masonry Drainage Structure (NCDOT Std. 840.04)           | EA   | 1                  |                |            |
| 39       | Masonry Drainage Structure (Custom Double CB)            | EA   | 1                  |                |            |
| 40       | 4' Diameter Manhole (COG Std. 612.03)                    | EA   | 1                  |                |            |
| 41       | Frame with Grate (NCDOT Std. 840.04)                     | EA   | 3                  |                |            |
| 42       | Frame with Grate and Hood (NCDOT Std 840.02)             | EA   | 16                 |                |            |
| 43       | Frame with Cover (Greenville Std. 614.03)                | EA   | 1                  |                |            |
| 44       | Concrete Endwall (NCDOT Std. 838.01)                     | EA   | 1                  |                |            |
| 45       | 12" RCP, Class III                                       | LF   | 5                  |                |            |
| 46       | 15" RCP, Class III                                       | LF   | 40                 |                |            |
| 47       | 15" RCP, Class IV  | LF   | 40                 |                |            |
| 48       | 18" RCP, Class III                                       | LF   | 60                 |                |            |
| 49       | 18" RCP, Class IV  | LF   | 80                 |                |            |
| 50       | 18" RCP, Class V   | LF   | 230                |                |            |
| 51       | 24" RCP, Class III                                       | LF   | 320                |                |            |
| 52       | 24" RCP, Class IV  | LF   | 210                |                |            |
| 53       | 24" RCP, Class V   | LF   | 130                |                |            |
| 54       | 30" RCP, Class IV  | LF   | 250                |                |            |
| 55       | 30" RCP, Class V   | LF   | 150                |                |            |
| 56       | Temporary Utility Support/Relocation                     | LS   | 1                  |                |            |
| 57       | 6-inch Diameter Restrained Joint Ductile Iron Water Main | LF   | 1,160              |                |            |
| 58       | Concrete Thrust Blocking Installation                    | CY   | 4                  |                |            |
| 59       | 2-Inch Resilient Wedge Gate Valve and Box                | EA   | 1                  |                |            |
| 60       | 4-Inch Resilient Wedge Gate Valve and Box                | EA   | 1                  |                |            |

City of Greenville  
 Cedar Lane Drainage Improvements  
 Hazen Project Number: 31187-003

| Item No.                                  | Description  | Unit | Estimated Quantity | Bid Unit Price | Bid Amount |
|---|--|------|--------------------|----------------|------------|
| 61  | 6-Inch Resilient Wedge Gate Valve and Box                  | EA   | 10                 |                |            |
| 62  | Ductile Iron Fittings                                      | LBS  | 1,000              |                |            |
| 63  | Item Removed   | N/A  | 0                  | \$0.00         | \$0.00     |
| 64  | Fire Hydrant w/GV and 6" DIP                               | EA   | 2                  |                |            |
| 65  | 6" Tapping Sleeve and Valve                                | EA   | 1                  |                |            |
| 66  | Relocate 2" Vault  | EA   | 1                  |                |            |
| 67  | Relocate 4" Water Service                                  | EA   | 1                  |                |            |
| 68  | Relocate 6" Water Service                                  | EA   | 2                  |                |            |
| 69  | Water Service, 2" and less                                 | EA   | 8                  |                |            |
| 70  | Connection to Existing Waterline                           | EA   | 5                  |                |            |
| 71  | PVC Sanitary Sewer Lateral Reconnection                    | EA   | 3                  |                |            |
| 72  | 6-Inch Ductile Iron Gravity Sewer (6'-8' Depth)            | LF   | 65                 |                |            |
| 73  | 8-Inch Ductile Iron Gravity Sewer (6'-8' Depth)            | LF   | 60                 |                |            |
| 74  | 10-Inch Ductile Iron Gravity Sewer (6'-8' Depth)           | LF   | 25                 |                |            |
| 75  | Connection of DI Gravity Sewer to VCP with Fernco Coupling | EA   | 9                  |                |            |
| 76  | Connection of Proposed Gravity Sewer to Existing Manhole   | EA   | 3                  |                |            |
| <b>Total of Base Bid Unit Price Items</b> |  |      |                    |                |            |