

Guy Smith Stadium Improvements Phase 1

Addendum No. 01



Project Name: Guy Smith Stadium Improvements	Project No.: RFP#23-24-12
Prepared By: Mark Nottingham	Date: 08-25-2023

Project Clarifications:

- The warning track shall be 10 feet wide and 4 inches in depth. The material to be used shall match existing.
- Salvage sod from the infield where the new warning track will be installed to cover the existing warning track impacted by moving the new fencing in.
- All new fencing and gates shall be galvanized to match existing fence.
- Some changes to new fence height will be proposed and spec'd in a revised plan sheet to be issued prior to bid date.
- The green vinyl fabric mesh shall be installed on the exterior fence panels/paywall.
- Relocation of existing irrigation controls and pump house will need to be included in this phase due to potential impacts from this project and Phase 2 improvements.