

**Wildwood Park Bridge and Boardwalk Package B
Addendum No. 01**



Project Name: Wildwood Park Bridge and Boardwalk	Project No.: RFP#23-24-13
Prepared By: Mark Nottingham	Date: 09-06-2023

Project Clarifications:

- Please incorporate a 1.25-inch (1.66-inch outside diameter (OD)) hot-dipped galvanized pipe railing on each side of the boardwalk exceeding 5% grade. Railing end section shall return to post. Railing shall be supported with galvanized brackets at each post. Railing shall be offset from face of post a min. 1.5-inches, mounted at 36-inches above the walking surface, & extend 1-foot beyond top & bottom of each ramp section. Each ramp section is approximately 30-feet.
- Please delete silt fencing for inundated areas & replace with sediment booms. Sediment booms may be relocated as active pile driving progresses along the length of the boardwalk to avoid purchasing & installing a continuous run for the entire length of boardwalk at once.